# GLENCORE

Gate Road Development Experience Using Continuous Haulage – 4FCT

**Glencore's Ulan West Mine** 

Longwall USA – Pittsburgh May 2019


# Agenda

- Glencore in Australia
- Ulan West Mine Overview
- Ulan West Mine Development History
- 4FCT Development system general arrangement
- 4FCT System performance data analysis MG03-MG05

GLENCORE

- Equipment Challenges / Major incidents
- Summary of findings
- Discussion / Questions

#### Glencore in Australia



GLENCORE

#### Australian coal operations






### Coal in NSW

**Ulan West Mine Location** 

Ulan West is an underground coal mine part of the Ulan Complex located approx. 4hrs west of Sydney and Newcastle in central NSW

Ulan West accesses the Port in Newcastle via rail for export







GLENCORE

#### Ulan West Mine

#### Background


Development of a new underground coal mine within the Ulan Coal Mines Complex

Located immediately west of current Ulan Underground

Extraction of coal using a high capacity longwall system (400m/1320ft wide)

LW Panels 1 - 12 range from 5.8km - 8km (3.7- 5 miles) in length with Block ROM 7-14Mt

Operate Monday – Friday Roster for production with a plan to produce 6-7Mt of ROM coal per year



## Ulan West Mine

**Current Operations** 

- 1. LW05 currently in operation Joy LW PRS, 7LS Shearer
- 2. MG06 Development Unit

Sandvik MB650 Miner, Joy 12CM30 Miner, 10SC42 Shuttle Car


3. MG07 Development Unit

Sandvik MB650 Miner, 10SC42 Shuttle Car

4. Mains Development

Joy 12CM30 Miner, 10SC43 Shuttle Car

4FCT Currently out of mine for Overhaul since completing MG05





## Ulan West Mine

**Development History** 

Panel Location	Mains / TG01 / MG01	MG02	MG03	MG04	MG05	MG06	MG07
Miner	12CM30	12CM30	12CM30	12CM30	MB650	MB650 12CM30	MB650
Haulage	Shuttle Car Feeder Breaker	Shuttle Car Feeder Breaker	4FCT	4FCT	4FCT	2 X Shuttle Car Feeder Breaker	Shuttle Car Feeder Breaker
Ventilation	Conventional	Monorail	Monorail	Monorail	Monorail	Conventional	Conventional
Power	Conventional	Monorail	Monorail	Monorail	Monorail	Conventional	Conventional

8

# 4FCT System General Arrangement


117

GLENCOR

5 060

### FCT System

#### **General Arrangement**







#### FCT System

**General Arrangement** 

Machine Logic..

#### FCT;

Mobile conveyor mounted on a traction chain Follows Continuous Miner through out pillar sequence Transfers coal from Continuous Miner to DMU Remote control operated


#### DMU;

Launch pad for FCT

Provides dynamic coal transfer point from FCT

Used to advance FCT and panel conveyor belt during panel advance

Remote control operated







#### 4FCT installation

Mine plans & Layout

#### Transport layout and installation for typical Gate Road Panel







# GLENCORE


# 4FCT Unit Performance Analysis MG03, MG04 and MG05

Statistics and Data

```
MG03 - 8,671m ≈ 28000ft
MG04 - 10,193m ≈ 34000ft
MG05 - 13,191m ≈ 44000ft
```

Data represents duration to cut total meters over 5 yr. period in three separate development units.


Data is inclusive of different roster patterns and strata conditions








#### Utilisation and Availability



GLENCORE

Advance Rate Improvement


- The advancement rate had increased resulting in a 16.6% decrease in the in the number of op time required to develop 100m
- The improvement has a direct correlation with the introduction of the FCT and the MB650 removing the Bolting constraint of the previous configuration







Cut rate – What Great Looks like




oh)


# System Challenges Key Learnings

#### System challenges / Key learning's - Operational

#### **Operational envelope considerations**

- Off line drivage effects with FCT/DMU/Monorail systems all in operational envelope
- System can tolerate 100mm of off line drivage
- DMU is 240m long and must be straight!!
- Monorail hanging bolt location is critical to ensure operation of trolleys









Operational envelope considerations – caused by monorail implementation

Mine explosion protection barrier (Bat Bags) requirements



Monorail was lowered to accommodate current bat bag design requirements however the Cut height had to be increased to 3.4m to prevent interaction

A new Low height bat bag was developed in the long term to resolve this issue for site




- Perceived complicated electrical and communication systems compared to conventional models
  - Leads to longer fault finding and increased skill requirements for trades
- Exposure to VVVF earth leakage issues due to the number of traction drives
  - OEM implemented developed drive stop system with the Joy VVVF Drive to remove the risk as part of implementation
- Mechanical Delays are more complicated and can have longer duration
  - ≻Chain brakes
  - Traction issues
  - Hydraulic issues

Overall the system has experienced less maintenance delays since implementation an has improved as a result of improvements

# Major Incident Learning Bootend Failure During Advance MG05

### Major Incident Learning

Bootend Failure During Advance MG05



In belt "lifted area" as DMU advances






### Major Incident Learning

Bootend Failure During Advance MG05

During the DMU Advance.....



The tail section moved out-bye approx. 18m.



### Major Incident Learning

Bootend Failure During Advance MG05


The incident was investigated with the Regulator and the OEM

Key Causal Findings identified

- Mechanical design
- Parameter management
- Procedures and systems of work

Following investigation both Joy (OEM) and Ulan West Mine implemented the necessary redesign's, upgrades and procedural changes to ensure that the incident would not be repeated in the future

 Detailed report available on NSW resource regulators website <u>https://</u> <u>www.resourcesregulator.nsw.gov.au/safety-and-health/incidents</u> <u>/investigation-reports</u>





GLENCORE

### Summary

compared to 2017

•

#### 4FCT Panel Performance - MG03, MG04, MG05



Availability of MG05 panel has increased

Maintenance (UM) has reduced by 7%

consistently over time, up by 10% in 2019 as

MG05 panel has experienced 19% less Planned

Maintenance (PM) than MG04, and Unplanned

#### Utilisation


Utilization has been trending downwards over the last 3 yrs.

Result of the increase cut rate, the faster the unit moves forward the more supporting activity needs to occur in advancing with the machine

### Productivity

16.6% reduction in operating hours required per 100 m development from MG04 to MG05

This uplift in productivity supports the improved cutting rate average over 5 moh





#### Summary

Was it all worth it?

Panel Type	Α	В
Miner	MB650	MB650
Haulage	Shuttle Car	4FCT
Ventilation	Conventional	Monorail
Power	Conventional	Monorail
Budget Advance Rate	3.18 moh	4.6 moh

4FCT combined with the MB650 delivers a rate increase of 44%

Ulan West Mine is currently working towards implementing the system into the next development panel





# Questions

